

**EXTRA ITEMS**

Name of Work: N/A

Name of Contractor or supplier: N/A

Reference to work order or Agreement: N/A

| Unit   | Quantity executed (or supplied) since last certificate | Quantity executed (or supplied) upto date as per MB | S. No. | Item of Work supplies (Grouped under "sub-head" and "sub work" of estimate)  | Rate  | Upto date Amount       | Amount Since previous bill (Total for each sub-head) | Remarks |
|--|--|---|--------|--|-------|------------------------|--|---------|
| nan  | 0  | 0   | 1.0    | Rewiring of light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper conductor 1.1 kV grade and 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper earth conductor 1.1 kV grade (IS:694) in recessed ISI marked MMS ( IS:9537 P - III ) virgin material PVC conduit & it's ISI marked (IS:3419-1988) accessories, round tiles, 1.2 mm thick MS box with earth terminal, 6 A switch, 3 pin ceiling rose/holder / 3 way connector , 3.0 mm thick ISI marked (IS:2036-1995) phenolic laminated sheet, Al.alloy / Cadmium plated iron/ brass screws, cup washers, making connections, testing etc. as required. For specification of copper Conductor, Phenolic Laminated sheet's & Electrical/ Wiring accessories refer Chapter E - 04, E - 05 & E - 07 For additional technical parameters of product / work refer Annexure 'A' attached with this BSR | 0     | 0                      | 0  |         |
| P. point   | 50.0   | 50.0  |        | Short point (up to 3 mtr.)   | 256.0 | 12800.0                | 12800.0  |         |
| P. point   | 50.0   | 50.0  |        | Medium point (up to 6 mtr.)  | 472.0 | 23600.0                | 23600.0  |         |
| P. point   | 50.0   | 50.0  |        | Long point (up to 10 mtr.)   | 662.0 | 33100.0                | 33100.0  |         |
| nan  | 0  | 0   | 2.0    | Rewiring of 3/5 pin 6 amp. Light plug point with 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper conductor 1.1 kV grade and 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper earth conductor 1.1 kV grade (IS:694) in recessed ISI marked MMS ( IS:9537 P - III ) virgin material PVC conduit & it's ISI marked (IS:3419-1988) accessories, 1.2 mm thick MS box with earth terminal of required size, 6 A switch, 3/5 pin 6 A socket, 3.0 mm thick ISI marked (IS:2036-1995) phenolic laminated sheet, Al.alloy / Cadmium plated iron/ brass screws, cup washers, making connections, testing etc. as required. For specification of copper Conductor, Phenolic Laminated sheet's & Electrical/ Wiring accessories refer Chapter E - 04, E - 05 & E - 07 For additional technical parameters of product / work refer Annexure 'A' attached with this BSR  | 0     | 0                      | 0  |         |
| P. point   | 100.0  | 100.0   |        | On board   | 136.0 | 13600.0                | 13600.0  |         |
| Each   | 10.0   | 10.0  | 3.0    | P & F ISI marked (IS:3854) 6 amp. flush type non modular switch with CM/L no. printed and made out from industrial grade Polycarbonate or fire resistant ABS material including cutting hole in tile and making connection testing etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .  | 23.0  | 230.0                  | 230.0  |         |
| nan  | 0  | 0   |        | Total  | 0     | 0                      | 0  |         |
| %  | 5.11   | 5.11  |        | Add Tender Premium   | 0     | 0                      | 0  |         |
| nan  | 0  | 0   |        | Grand Total  | 0     | 0                      | 0  |         |
|  |  |   |        | Grand Total Rs.  |       | 87588.163              | 87588.163  |         |
|  |  |   |        | Tender Premium @ 5.11%   | 5.11% | 4258.163000000<br>0005 | 4258.163000<br>0000005                               |         |
| Sum of Extra Items (including Tender Premium): NIL |  |   |        |  |       |                        |  |         |
|  |  |   |        | Payable Amount Rs.   |       | 87588.163              | 87588.163  |         |
|  |  |   |        | Less Amount Paid vide Last Bill Rs.  |       | 0.00                   | 0.00   |         |
|  |  |   |        | <b>Net Payable Amount Rs.</b>  |       | <b>87588.16</b>        | <b>87588.16</b>                                      |         |

**Certified that:**

The extra items listed above have been actually executed and measured.

The rates quoted are as per the schedule of rates of the work order or as agreed.

The work has been carried out in accordance with the terms and conditions of the agreement.

All deductions as per rules have been made.

**Prepared by:** \_\_\_\_\_

Name: \_\_\_\_\_

Designation: \_\_\_\_\_

Date: \_\_\_\_\_

**Checked by:** \_\_\_\_\_

Name: \_\_\_\_\_

Designation: \_\_\_\_\_

Date: \_\_\_\_\_

**Authorized Signatory:** \_\_\_\_\_  
Name: \_\_\_\_\_  
Designation: \_\_\_\_\_  
Date: \_\_\_\_\_